CR: 1161 - GUANAJUATO MODULO ADUANAL -

A&R CONSTRUCCIONES SA DE CV

EMPRESA:

	IMPORTE CONTRATADO				
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE
ADC-004	SANITARY OUTPUT FOR CONDENSING UNIT WITH PIPE AND HYDRAULIC PVC CONNECTIONS OF	SAL	2.000000	\$ 719.75	\$ 1,439.49
	19 MM DIAMETER, GLUE, ELBOWS, TEES, CONNECTORS, REDUCTIONS. INCLUDES: HANGING,				
	MATERIALS TO THE SITE OF THE WORK, VERTICAL AND HORIZONTAL TRANSPORTATION AT				
	ANY LEVEL, TRACE AND LEVELING, MATERIAL, WASTE, SPECIALIZED HAND TOOL, TOOL,				
	SAFETY REQUIREMENTS, PERSONAL SAFETY EQUIPMENT, PLACEMENT OF BARRIER TAPE,				
	INSTALLATION OF PROTECTION TO ADJACENT AREAS AND ITS WITHDRAWAL AFTER USE,				
	WITHDRAWAL OF THE REMOVABLE MATERIALS OUTSIDE THE WORK AND ALL NECESSARY FOR				
	THE CORRECT PERFORMANCE				
ADC-003	SUPPLY AND INSTALLATION OF COPPER TUBE TYPE "L" FLEXIBLE NACOBRE MARK OF 1/2 "OF	М	15.000000	\$ 611.12	\$ 9,166.83
	Ø, PLACED AT ANY LEVEL AND AT ANY LEVEL, THE PRICE INCLUDES: CODES, COPLES,				
	REDUCTIONS, TEES, YEES, UNION NUT, THERMAL INSULATION TYPE INSOLTUBE OF 3/4 ",				
	CHARGING OF REFRIGERANT GAS R-410A, SILVER WELDING 15% TYPE HARRIS, FOUND PASTE,				
	LIJA, CUTS, LEVELS, WELDING EQUIPMENT, ELBOWS, TEES, COPLES, SUPPORT STRUCTURE				
	ACCORDING TO PLAN AND CONCEPT, MISCELLANEOUS AND CONSUMPTION MATERIALS,				
	PERSONAL PROTECTIVE EQUIPMENT, TOOLS, SCAFFOLDING, LIFTING, LOADING,				
	DOWNLOADING AND CLEANING OF THE PLACE OF EXECUTION.				
ADC-002	SUPPLY AND INSTALLATION OF THERMOSTAT BRAND HONEYWELL MODEL TH8320, INCLUDES:	PZA	2.000000	\$ 4,979.76	\$ 9,959.51
	THERMOSTAT GUARD, OPERATING TESTS, SPECIALIZED WORK HAND, SUPPORTERS,				
	MOUNTING AT ANY LEVEL, ADJUSTMENT AND LEVELING, FLOWS AND HANDLINGS, ADAMS,				
	SAFETY EQUIPMENT AND TOOLS, CLEANING OF THE AREA OF WORK AND ALL NECESSARY				
	FOR THEIR CORRECT INSTALLATION.				
ADC-001	ELECTRIC OUTPUT MINI SPLIT TUBE-BASED CONDUIT GALVANIZED PG FROM 13MM TO 35MM	SAL	2.000000	\$ 2,207.66	\$ 4,415.32
	WITH DEVELOPMENTS ACCORDING TO DISTRIBUTION IN PLANS UP TO 10M AVERAGE EXIT TO				
	THE BOARD, WITH AWG CABLES CAL- 6 TO 12, WITH THERMAL INSULATION PLASTIC THW-LS 90				
	°, 600 V, AND CABLE NAKED CAL. 8 TO 12, INCLUDES: SQUARE BOXES, BOXES BOXES, COPLES,				
	ELBOWS, SUPPORT STRUCTURE @ 1.5 MTS ON BASE OF THREADED ROD NO. 10, "U" CLAMP,				
	HILTI BOLT AND NUTS, CONNECTORS, COVER, SUPPLY OF MATERIALS, QUALIFIED WORK				
	HAND, TOOL AND ALL NECESSARY FOR ITS CORRECT PERFORMANCE				
IE-009	SUPPLY AND INSTALLATION OF BOARD SQUARE D QO-08-16L, INCLUDES: SUPPLY AND	PZA	1.000000	\$ 1,987.35	\$ 1,987.35
	INSTALLATION, FINAL TESTS, CLEANING OF THE WORK AREA AND REMOVAL OF OUTSIDE				
	MATERIALS OUTSIDE THE WORK WITH FREE SHOT, AS WELL AS THE HAND WORK NECESSARY				
	FOR ITS CORRECT TERMINATION .				
IE-008	SUPPLY AND INSTALLATION OF THERMOMAGNETIC SWITCH MARK SQUARE D MODEL QOB-115,	PZA	4.000000	\$ 217.76	\$ 871.06
	1 POLE, 15 AMPERES, 240 VOLTS, INCLUDES: CONNECTION, IDENTIFICATION, HANDLING, TOOL,				
	SAFETY AND PROTECTIVE EQUIPMENT AND ALL NECESSARY FOR THEIR CORRECT				
	INSTALLATION. CONSIDER NECESSARY SAFETY EQUIPMENT AND COMPLIANCE WITH THE				
	RESPECTIVE STANDARD FOR THE CORRECT EXECUTION OF THE CONCEPT.				
IE-007	SUPPLY AND INSTALLATION OF CONTACT POLARIZED DUPLEX WITH INSULATED PHYSICAL	PZA	10.000000	\$ 227.45	\$ 2,274.54
	GROUND CONNECTION, HUBBELL BRAND, MODEL IG2310A, NEMA 5-20R, 20 AMP, 127 VOLTS, 60				
	HZ., COLOR: ORANGE, FOR RACK, CONCEPT INCLUDES, PLACEMENT, CONNECTION, POLARITY				
	TEST, QUALIFIED WORK HAND, TOOL, SAFETY EQUIPMENT AND PROTECTION AND ALL				
	NECESSARY FOR THEIR CORRECT INSTALLATION.				
IE-006	ELECTRICAL OUTPUT FOR CONTACTING PVC-TUBE CONDUIT LIGHT FROM 13MM TO 21MM WITH	SAL	12.000000	\$ 1,302.24	\$ 15,626.86
	DEVELOPMENTS ACCORDING TO DISTRIBUTION IN PLANS OF UP TO 5M AVERAGE OUTPUT TO				
	BOARD, WITH AWG CABLES CAL- 10 TO 12, WITH THERMAL INSULATION THW-LS PLASTIC 90 °,				
	600 V, Y NUDE CABLE CAL. 10 TO 12, INCLUDES: SQUARE BOXES, CHALUPAS BOXES, CUPS,				
	ELBOWS, SUPPORT STRUCTURE @ 0.90 OR 1.5 MTS AS INDICATED IN A PROJECT BASED ON				
	THREADED RODNER NO. 10, "U" CLAMP, HILTI BOLT AND NUTS, CONNECTORS, COVER, SUPPLY				
	OF MATERIALS, QUALIFIED WORK HAND, TOOL AND ALL NECESSARY FOR ITS CORRECT				
	PERFORMANCE				

CR: 1161 - GUANAJUATO MODULO ADUANAL -

A&R CONSTRUCCIONES SA DE CV

EMPRESA:

			1.0.1.2		
	IMPORTE CONTRATADO				
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE
IE-005	SUPPLY AND INSTALLATION OF POLARIZED DUPLEX CONTACT WITH INSULATED PHYSICAL	PZA	10.000000	\$ 385.82	\$ 3,858.18
	GROUND CONNECTION, HUBBELL BRAND, MODEL IG2310A, NEMA 5-20R, 20 AMPERES, 127				
	VOLTS, 60 Hz., COLOR: ORANGE FOR RACK, THE CONCEPT INCLUDES, COVER ACCORDING TO				
	PROJECT, PLACEMENT, CONNECTION, POLARITY TEST, QUALIFIED WORK HAND, TOOL, SAFETY				
	AND PROTECTION EQUIPMENT AND ALL NECESSARY FOR THEIR CORRECT INSTALLATION.				
IE-004	ELECTRICAL OUTPUT FOR CONTACTING PVC-TUBE CONDUIT LIGHTWEIGHT FROM 13MM TO	SAL	10.000000	\$ 1,293.93	\$ 12,939.26
	21MM WITH DEVELOPMENTS ACCORDING TO DISTRIBUTION IN PLANS OF UP TO 5M AVERAGE				
	OUTPUT TO BOARD, WITH AWG CABLES CAL- 10 TO 12, WITH THERMAL INSULATION THW-LS				
	PLASTIC 90 °, 600 V, Y NUDE CABLE CAL. 10 TO 12, INCLUDES: SQUARE BOXES, CHALUPAS				
	BOXES, CUPS, ELBOWS, SUPPORT STRUCTURES @ 0.90 OR 1.5 MTS AS INDICATED IN A				
	PROJECT BASED ON THREADED RODNER NO. 10, "U" CLAMP, HILTI BOLT AND NUTS,				
	CONNECTORS, CONTRATAPA, SUPPLY OF MATERIALS, QUALIFIED WORK HAND, TOOL AND ALL				
	NECESSARY FOR ITS CORRECT PERFORMANCE				
IE-003	SUPPLY AND INSTALLATION OF B-TICIÑO MAGIC C / 2-UNIT PLATE, INCLUDES SUPPLY,	PZA	4.000000	\$ 73.86	\$ 295.46
	INSTALLATION AND TESTS REQUIRED FOR THEIR CORRECT INSTALLATION				
IE-002	SUPPLY AND INSTALLATION OF LUMINAIRE IN CEILING 121X61 CM BRAND MCA CONSTRULITA	PZA	12.000000	\$ 4,212.00	\$ 50,544.00
	OF 1028B41A.				
IE-001	ELECTRICAL OUTPUT FOR LIGHTING BASED ON PVC TUBE CONDUIT LIGHTWEIGHT FROM 13MM	SAL	16.000000	\$ 657.70	\$ 10,523.14
	TO 21MM WITH DEVELOPMENTS ACCORDING TO DISTRIBUTION IN PLANS OF UP TO 4M				
	AVERAGE OUTPUT TO THE BOARD, WITH AWG CABLES CAL- 10 TO 12, WITH THERMAL				
	INSULATION THW-LS PLASTIC 90 °, 600 V, Y NUDE CABLE CAL. 10 TO 12, INCLUDES: SQUARE				
	BOXES, CHALUPAS BOXES, CUPS, ELBOWS, SUPPORTING STRUCTURES @ 0.90 OR 1.5 MTS AS				
	INDICATED IN A PROJECT BASED ON THREADED RODNER NO. 10, "U" CLAMP, HILTI BOLT AND				
	NUTS, CONNECTORS, CONTRATAPA, SUPPLY OF MATERIALS, QUALIFIED WORK HAND, TOOL				
	AND ALL NECESSARY FOR ITS CORRECT PERFORMANCE				
IHS-004	NON-ASCENDANT SPINDLE VALVE FIGURE 83 OF 32 MM URREA BRAND INCLUDES: SUPPLY AND	PZA	1.000000	\$ 412.73	\$ 412.73
	INSTALLATION, SUPPORTERS, CLEANING OF THE WORK AREA, AND THE MANEUVERS				
	NECESSARY FOR THEIR CORRECT TERMINATION.				
IHS-003	SANITARY OUTLET FOR TARJA, WITH PIPE AND PVC MCA CONNECTIONS. DURALON OF 50 MM.	SAL	1.000000	\$ 1,093.57	\$ 1,093.57
	OF DIAMETER, GLUE, ELBOWS, TEES, YEES, REDUCTIONS, LID REGISTRY, PVC VENTILATION				
	PIPE OF 50 MM. OF DIAMETER, PERFORATIONS, SLOTS, RESEARCH, FIXING AND				
	CONSUMPTION MATERIALS. INCLUDES: CARRYING MATERIALS TO THE SITE OF THE WORK,				
	VERTICAL AND HORIZONTAL TRANSPORTATION AT ANY LEVEL, TRACE AND LEVELING,				
	MATERIAL, WASTE, SPECIALIZED HAND TOOL, TOOL, SAFETY REQUIREMENTS, PERSONAL				
	SAFETY EQUIPMENT, PLACEMENT OF BARRICATED TAPE , INSTALLATION OF PROTECTION TO				
	THE ADJACENT AREAS AND ITS WITHDRAWAL AFTER THEIR USE, REMOVAL OF THE				
	REMOVABLE MATERIALS OUTSIDE THE WORK AND ALL NECESSARY FOR THE CORRECT				
	PERFORMANCE. INTERNAL CARRIERS AND CLEANING OF THE CONCEPT				
IHS-002	HYDRAULIC OUTPUTS FOR TARJAS, INCLUDES: THE DIRECT COST OF THE MATERIALS,	SAL	2.000000	\$ 1,512.25	\$ 3,024.50
	FREIGHT AND CARRYING TO THE SITE OF USE, CASE COVER, ANGLE VALVE, WELDING, FOUND				
	PASTE, TYPE M COPPER PIPE, CONNECTIONS, PLACEMENT, FIXATION, LEVELING, WORK				
	HANDLING, SAFETY EQUIPMENT, CONSUMER MATERIALS, PRELIMINARY CLEANING OF THE				
	WORK AREA TESTS AND REMOVAL OF THE SURFACE MATERIALS TO THE WORKBANK. TOOLS,				
	EQUIPMENT, INTERNAL CARRIAGE AND OWN CLEANING OF THE CONCEPT.				
IHS-001	SUPPLY AND INSTALLATION OF TARJA FOR COFFEE. MCA TEKA, 0.80 X 0.45 MTS. WITH	PZA	2.000000	\$ 7,446.07	\$ 14,892.14
	STAINLESS STEEL DRAINER MOD. 800.510 1C-1E, DRAIN OF 3/12 OF 3 HOLES FOR GRIFFERY				
	VERSION LEFT, WITH AGAINST CANVAS MCA. HELVEX MOD. H-8801 AND KEY MACHINING MCA.				
	HELVEX, MOD. NOVUS E-34 COLOR CHROME FOR CARDS, INCLUDES: CLEANSER, SLOTS,				
	RESEARCH, TOOL, LABOR, SAFETY EQUIPMENT, CLEANING OF THE WORK AREA AND ALL				
	NECESSARY FOR THEIR CORRECT PLACEMENT AND GOOD OPERATION				

CR: 1161 - GUANAJUATO MODULO ADUANAL - A&R CONSTRUCCIONES SA DE CV

	IMPORTE CONTRATADO				
ÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE
IM-001	FINAL CLEANING OF WORK FOR DELIVERY-RECEIVING, INCLUDES: CLEANING OF FLOORS,	M2	135.000000	\$ 24.74	\$ 3,339.37
	PLAFONS, FURNITURE, SANITARY FURNITURE, ALUMINUM AND CRYSTAL CANCELING, WALLS,				
	AND ALL THE NECESSARY ELEMENTS THAT INTERVENE IN THE WORK, DETERGENTS,				
	MURIATIC ACID, WATER, IN THIS CONCEPT SHOULD INCLUDE THE REMOVAL OF ALL				
	SOFTWARE MATERIALS THAT WERE USED FOR THE EXECUTION OF THE DIFFERENT WORK OF				
	THE WORK OUTSIDE THE WORK AREA, THE SAME INCLUDING CHARGE AND DISCHARGE				
ED 004	THEMSELVES FREE SHOT, AND WHAT IS NECESSARY FOR ITS TERMINATION.	D74	4.000000	0.0.474.40	<b>0.7.005.04</b>
ER-001	SUPPLY, PLACEMENT AND MANUFACTURE OF INTERCOMMUNICATION METALLIC DOOR,	PZA	4.000000	\$ 9,471.40	\$ 37,885.61
	INCLUDES: TOPS, CUTLERY, INTERCOMMUNICATION PLATE, BOOK HINGE BOLTS BOLT,				
	CLEANING OF WORK AREA AND REMOVAL OF OUTSTANDING MATERIALS OUTSIDE THE WORK				
	WITH FREE SHOT, AS WELL AS THE HAND WORK NEEDED FOR THEIR CORRECT TERMINATION.				
	DE 0.90 X 2.10M. MATERIAL, HAND WORK, TOOLS, EQUIPMENT, INTERNAL CARRIAGE AND OWN				
AD 000	TRACK OF THE CONCEPT.	NAI.	0,000000	<b>↑</b> C C 4 O O O	# 20 0FC 0C
AR-002	SUPPLY AND PLACEMENT OF COFFEE CABIN COVER IN GRANITE.	ML	6.000000	\$ 6,642.80	\$ 39,856.80
AR-001	SUPPLY OF BAR COFFEE DIMENSIONS 0.60 WIDTH FABRICATION BASED ON 1A PINE WOOD	ML	8.500000	\$ 3,840.00	\$ 32,640.00
	FRAME. OF 1 1/2 "" X 1 1/2 "LINED WITH WOODEN PINE TRIPLAY OF 1 MM OF 6 MM NOSE				
	STICKED OF 5 CM OF RADIO, FINISHED WITH PLASTIC LAMINATE FORMICA BRAND 459-58				
	BRITE.WHITE, STRUCTURES AND 19 MM MDF SIDES WALLED IN BOTH SIDES AND VISIBLE				
	CANTOS COMPLETED WITH FORMICA BRAND PLASTIC LAMINATING, INCLUDES: WOODEN CAN				
	OF 1 1/2 "X 1" @ 50 CM, CUTTING, WASTE, GLUE, FREIGHT, MATERIAL HARVESTING, TOOL,				
	LABOR, CLEANING AND REMOVAL OF REMOVERS OUTSIDE THE WORK, SAFETY EQUIPMENT.				
:AN-002	MATERIALS, INTERNAL CARRYING, TRACING AND CLEANING OF THE CONCEPT.	PZA	1.000000	¢ 10 507 04	¢ 40 507 07
AIN-002	SUPPLY AND PLACEMENT OF INTERIOR DOORS BASED ON LAMINATED CRYSTAL COMPOSED BY TWO LIGHT CRYSTALS FLOATED OF 6MM DEAD FILOS, MORE POLYVINYL BUTIRAL-PVB FILM	PZA	1.000000	\$ 12,587.04	\$ 12,587.04
	OF 0.89 MM MCA. DUPONT, FRAMED WITH ALUMINUM PROFILES TYPE BAG 3 "X 1 3/4", AND 3/4				
	"RACK, DIMENSIONS 0.85 UP TO 1.22 WIDE AND FROM 2.00 TO 2.44M HIGH, INCLUDES: PHILLIPS				
	BRAND LOCK MOD. 530 AN , PIVOT PHILLIPS MOD 3300 AN, PRECISION MECHANICAL CUTS, SLOTS IN FLOOR AND PLACEMENT TO LEAD, LEVEL AND SQUARE, SEAL OF PERIMETER VINYL,				
	LEAD SHOULDER, FIXING MATERIALS, SPECIALIZED HAND TOOL, TOOL, SAFETY EQUIPMENT, I				
	WILL ATTACH ANY LEVEL WITHIN THE WORK TO THE STATION OF OPERATION DETERMINED,				
	FINAL CLEANING OF THE AREA OF WORK AND CLEANING OF ANY WASTE OF THE AREA IN USE				
	AND ADJACENT AND ALL NECESSARY FOR ITS CORRECT PERFORMANCE				
AN-001	SUPPLY AND PLACEMENT OF LAMINATED CRYSTAL COMPOSED BY A CLEAR GLASS TEMPERED	M2	25.000000	\$ 3,536.25	\$ 88,406.28
AIN-UU I	OF 6MM FILOS MUERTOS, MORE FILM SGP OF 0.89 MM (BEFORE PVB OF 1.52 MCA. DUPONT),	IVIZ	25.000000	φ 3,330.23	φ 66,406.26
	MORE CLEAR TEMPERED GLASS OF 6MM DEAD FILES, WITH ALUMINUM VAGET ANODIZED				
	NATURAL 2 "X1", INCLUDES: LEVELING, LEAD SHOES, VINYL SEAL, SILICON, SCREW, VERTICAL				
	AND HORIZONTAL TOOLS, SPECIALIZED HAND TOOL, TOOL, EQUIPMENT, ADJACENT WORK				
	AREA PROTECTION, WORK AREA CLEANING AND ALL NECESSARY FOR THEIR CORRECT				
	TERMINATION. FLOOR A919, A919B.				
CA-003	MODULAR FALSE CEILING MATERIALS SUPPLY BRAND USG MODEL RADAR 61 X 61 CM. WITH	M2	135.000000	\$ 370.84	\$ 50,062.86
OA 003	VISIBLE SUSPENSION LINE OF SHADOW MCA. ARMSTRONG. INCLUDES:, SUSPENSION,	IVIZ	155.000000	ψ 37 0.04	Ψ 30,002.00
	HANGING, ANGLE PERIMETER, FREIGHT, TRANSPORTATION, STORAGE, CLEANING WORK AREA				
	AND REMOVAL OF MATERIALS LEFTOVERS OUT OF THE WORK WITH A FREE KICK, AS WELL AS				
	THE REQUIRED MANEUVERS TO ITS PROPER COMPLETION. LABOR, TOOLS, EQUIPMENT AND				
	CLEANING OF THE CONCEPT ITSELF				
CA-002	SUPPLY AND APPLICATION OF PAINT ACQUA 100 MATTE WHITE, MCA. COMEX WITH MIXTURE	M2	230.000000	\$ 125.27	\$ 28,812.39
J, , 00Z	OF PASTE TO MATCH FINISH THERE. INCLUDES:, TWO COATS MINIMUM OF PAINTING, A HAND	IVIZ	200.000000	Ψ 120.21	Ψ 20,012.38
	OF SEALANT VINYL 5 X 1, PREPARATION OF THE SURFACE, CLEANING OF THE WORK AREA				
	AND REMOVAL OF LEFTOVERS OUT OF THE WORK WITH THROW MATERIALS FREE TO ANY				
	HEIGHT, AS WELL AS THE REQUIRED MANEUVERS TO ITS CORRECT TERMINATION. MATERIAL,				
	LABOR, TOOLS, EQUIPMENT, INTERNAL TRANSPORTATION AND CLEANING ITSELF OF THE				
	E 1001, 10010, EQUI MENT, INTENNAL TRANSPORTATION AND GLEANING TIGHT OF THE				

FMPRFSA. CR: 1161 - GUANAJUATO MODULO ADUANAL -A&R CONSTRUCCIONES SA DE CV **IMPORTE CONTRATADO** CÓDIGO **CONCEPTO** UNIDAD CANTIDAD P.U. **IMPORTE** ACA-001 SUPPLY AND PLACEMENT OF TYPE Z3, BLACK VINYL WALL BASE OF 4 "(10CM) MARK VINYLASA М 45.000000 \$ 87.18 \$ 3,923.12 MOD. TCB-66 EITHER ORE INCLUDES: CUTS, WASTE, ADJUSTMENTS, CLEANING OF THE WORK AREA AND REMOVAL OF LEFTOVERS OUT OF THE WORK WITH A FREE KICK, AS WELL AS MATERIALS NECESSARY MANOEUVRES TO ITS PROPER COMPLETION, LABOR, TOOLS. EQUIPMENT INTERNAL TRANSPORTATION AND CLEANING ITSELF OF THE CONCEPT ALB-005 CONSTRUCTION OF WALL OF PARTITION'S BLOCK OF 12 X 20 X 40 CM. MINIMUM, SEATED WITH M2 130.000000 \$ 471.98 \$ 61,357.46 MORTAR CEMENT-SAND MORTAR JOINT FINISHING 1:4: B) 12 CM. WIDE. INCLUDES: INTERNAL CARRIES MATERIAL HAND WORK TOOLS FOLLIPMENT AND CLEANING OF THE CONCEPT ITSELE AI B-004 CONSTRUCTION OF ARMED CONCRETE CASTLE F'C=150KG/CM2 OF 15X15CM, WITH 4 TO @3/8 М 50.000000 \$ 292 49 \$ 14,624.62 YE 1/4"@ 20CM INCLUDES CIMBRA STEEL ENABLED CONCRETE DRAINING DECORATION WATER CURE, WORK AREA CLEANING AND REMOVAL OF OUTSIDE MATERIALS FROM THE WORK, AS WELL AS THE HAND WORK NEEDED FOR THEIR CORRECT TERMINATION. MATERIAL, TOOL, EQUIPMENT AND INTERNAL CARRIAGE. ALB-003 \$ 316.23 \$41,109,34 CONSTRUCTION OF CONCRETE PLATFORM CHAIN AND CLOSURE OF 15 X 20 CM, CONCRETE М 130.000000 F'C = 150 KG/CM2 WITH 4 @ 3/8 "AND 1/4" @ 20 CM., INCLUDES: FORMWORK, STEEL ENABLED, POURING CONCRETE, DESCIMBRA, CURED WITH WATER, CLEANING OF THE WORK AREA AND REMOVAL OF MATERIALS LEFTOVERS OUT OF THE WORK WITH A FREE KICK. AS WELL AS THE REQUIRED HANDLING TO ITS PROPER COMPLETION. MATERIALS, HANDLING, TOOLS, **EQUIPMENT AND INTERNAL SCREE** ALB-002 TRACKING AND LEVELING OF THE LOCAL, INCLUDES: BANK OF LEVELS, HORIZONTAL. M2 250 000000 \$ 156 83 \$ 39 207 46 LONGITUDINAL AND TRANSVERSAL REFERENCES. AS WELL AS THE GRAPHIC INDICATION THROUGH PIGEONS IN THE DIFFERENT AXLES WHERE REQUIRED BASED ON YELLOW TRAFFIC COLOR ENAMEL AND WITH THE REFERENCE OF THE LEVEL BANK WITH NUMBERS OF 5CM. OF HEIGHT AS WELL AS NECESSARY FOR THE CORRECT TERMINATION, FREIGHT AND HANDLING. THE NEEDED HAND, TOOL, TENDERS, SAFETY EQUIPMENT, PRELIMINARY CLEANING OF WORK AREA AND REMOVAL OF SURFACES TO THE BANK OF THE WORK. ALB-001 М \$ 132 30 \$ 661 48 CONSTRUCTION OF GROOVE IN FLOOR OF REINFORCED CONCRETE OF 0.10 X 0.20/0.25 M. 5 000000 INCLUDING: REPAIR WITH CONCRETE F'C = 100 KG/CM2, CLEANING OF THE WORK AREA AS WELL AS THE REQUIRED HANDLING TO ITS PROPER COMPLETION, MATERIALS, LABOR, TOOL FOLIPMENT AND INTERNAL TRANSPORTATION PRE-002 TRACKING AND LEVELING OF THE LOCAL, INCLUDES: BANK OF LEVELS, HORIZONTAL, M2 135.000000 \$ 9.64 \$ 1.301.47 LONGITUDINAL AND TRANSVERSAL REFERENCES. AS WELL AS THE GRAPHIC INDICATION THROUGH PIGEONS IN THE DIFFERENT AXLES WHERE REQUIRED BASED ON YELLOW TRAFFIC COLOR AND WITH THE REFERENCE OF THE BANK OF LEVEL WITH NUMBERS OF 5CM, OF HEIGHT AS WELL AS NECESSARY FOR THE CORRECT TERMINATION, FREIGHT AND HANDLING, THE NEEDED HAND, TOOL, TENDERS, SAFETY EQUIPMENT, PRELIMINARY CLEANING OF WORK AREA AND REMOVAL OF SURFACES TO THE BANK OF THE WORK PRF-001 RETIREMENT OF RUBISH IN TRUCK, OUTSIDE THE WORK, OF MATERIALS, DEMOLITIONS M3 1 000000 \$ 346 25 \$ 346 25 PRODUCT. INCLUDES: CHARGE AND DISCHARGE OF TRUCK, SPECIALIZED WORK HANDLING, TOOLS. SAFETY REQUIREMENTS, PERSONAL SAFETY EQUIPMENT, PLACEMENT OF BARRIER TAPE, INSTALLATION OF PROTECTION TO ADJACENT AREAS AND ITS WITHDRAWAL AFTER ITS USE AND ALL NECESSARY FOR ITS CORRECT PERFORMANCE, MATERIAL, EQUIPMENT, CARRYING AND CLEANING ADC-005 SUPPLY AND INSTALLATION OF VITOCERAMIC GRILL 30CM IO MABE IO312DVI0 AND ALL Ρ7Δ 4 000000 \$871510 \$ 34 860 38

NECESSARY FOR THE CORRECT PERFORMANCE

TOTAL DE PRESUPUESTO ADICIONALES

Importe Contratado=	\$0.00				

Deductivas= \$0.00

\$ 634,305,87

			EMPRESA:				
CR: 1161 - GUANAJUATO MODULO ADUANAL -		A&R CONSTRUCCIONES SA DE CV					
	IMPORTE CONTRATADO						
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE		

Items fuera de catálogo=

			EMPRESA:		
CR: 1161 - GUANAJUATO MODULO ADUANAL -		A&R CONSTRUCCIONES SA DE CV			
	IMPORTE CONTRATADO				
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE
					\$ 634,305.87

			EMPRESA:			
CR: 1161 - GUANAJUATO MODULO ADUANAL -		A&R CONSTRUCCIONES SA DE CV				
IMPORTE CONTRATADO						
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE	

Penalización por incumplimiento de fechas contractuales=

		EMPRESA:			
CR: 1161 - GUANAJUATO MODULO ADUANAL -		A&R CONSTRUCCIONES SA DE CV			
	IMPORTE CONTRATADO				
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE
					\$0.00

			EMPRESA:				
CR: 1161 - GUANAJUATO MODULO ADUANAL -		A&R CONSTRUCCIONES SA DE CV					
	IMPORTE CONTRATADO						
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE		

Subtotal=

			EMPRESA:		
CR: 1161 - GUANAJUATO MODULO ADUANAL -		A&R CONSTRUCCIONES SA DE CV			
	IMPORTE CONTRATADO				
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE
					\$ 634,305.87

		EMPRESA:				
CR: 1161 - GUANAJUATO MODULO ADUANAL -		A&R CONSTRUCCIONES SA DE CV				
IMPORTE CONTRATADO						
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE	

A&R CONSTRUCCIONES SA DE CV

			EMPRESA:				
CR: 1161 - GUANAJUATO MODULO ADUANAL -		A&R CONSTRUCCIONES SA DE CV					
	IMPORTE CONTRATADO						
CÓDIGO	CONCEPTO	UNIDAD	CANTIDAD	P.U.	IMPORTE		

BOVIS